KADUR DIVISION.

Dated 4th December 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 1 P.M., on 9th January 1931, for constructing (1) Chattram, (2) Veterinary Hospital and three blocks of officials' quarter at Kalasa, Mudgere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11-30 A.M. and 5 P.M. on working days.

3. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing (1) a Chattram, (2) Veterinary Hospital and three blocks of officials' quarters at Kalasa, Mudgere Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, of Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The rate should be noted for each item of work.

10. Percentage quotations either below the lowest tender or sanctioned estimated amount will not be accepted.

11. The contract must not be sublet.

12. No claims for enhanced rate will be preferred after tender is accepted and during the course of execution of work.

13. In all matters of dispute regarding quality of work, rates, etc., the decision of the Superintending Engineer, Shimoga Circle, is final and legally binding.

Approximate quantities for constructing the above buildings.

Approximate quantities for constructing a Chattram at Kalasa, Mudgere Taluk.

Serial No.	Particulars of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
1	Earthwork excavation and filling in basement including watering, etc.	C.yd.	61		
2	Stone jelly concrete in chunam mortar ...	C.ft.	668		
3	Rough stone in mud foundation and basement	,,	1,327		
4	Burnt brick in mud superstructure ...	,,	1,983		
5	Burnt brick in mortar ...	,,	524		
6	Burnt stone slabs 4½" to 6" dress ...	S.ft.	137		
7	Nandiwood wrought and put up including wood oiling.	C.ft.	127·18		
8	Nandiwood battened door with double shutters 1" thick including frame, iron fitting, etc.	S.ft.	117		
9	Nandiwood battened windows with double shutters including iron bars, fittings, etc., complete	,,	144		
10	Pointing the basement with chunam ...	Sqr.	3·50		
11	Plastering with chunam	,,	50·21		
12	White and colour washing	,,	50·21		
13	Silicate painting to doors and windows 2 coats.	,,	5·22		
14	Roofing with 1st Class Mangalore tiles on teak reepers including nailing, etc.	,,	22·57		
15	Poviding and fixing 1st Class Mangalore ridge tiles set in mortar including cement pointing.	R.ft.	132		

Serial No.	Particulars of work	Per	Quantity	Rate	
				In figures	In works
				Rs. a. p.	
16	Flooring with 3" gravel including lead, watering, tamping and cowdung wash.	Sqr.	9·00		
17	Providing and fixing Nandi wood eave board (plain) 9" long including wood oiling.	R.ft.	34		
18	Clearing site, brick bonds over roof at ends and unforeseen items.	Lump sum			
19	Zinc sheet and teak plank for valleys with cement border at top, plastering, etc., complete.	R.ft.	29		
	Approximate quantities for constructing a Veterinary Hospital at Kalasa, Mudgere Taluk.				
				Rs. a. p.	
1	Earthwork excavation and filling in basement	C.yd.	41		
2	Stone jelly concrete in chunam mortars	C.ft.	494		
3	Rough stone in mud foundation and basement.	,,	888		
4	Burnt brick in mud superstructure ...	,,	1,581		
5	Nandiwood battened door with double shutters 1" thick, iron fittings, etc., complete.	S.ft.	91		
6	Nandiwood battened windows with double shutters, panelled outside and glazed inside with iron bars, hinges, etc., complete.	,,	56		
7	Nandiwood gate including iron fittings, etc., complete.	No.	1		
8	Burnt stone slabs dressed 6" thick roughly dressed.	S.ft.	115		
9	Burnt stone slab pillars (6" x 1') nicely dressed and champered at edges.	No.	4		
10	Cutting grooves in stone pillars ...	,,	4		
11	Nandiwood wrought and put up including wood oiling.	C.ft.	72·76		
12	Roofing with 1st Class Mangalore tiles on 1" teak reepers including nailing, etc.	Sqr.	12·50		
13	Silicate painting two coats	,,	3·69		
14	Chunam plastering two coats	,,	31·65		
15	Providing 1st Class Mangalore ridge tiles including fixing in mortar and cement pointing.	R.ft.	88		
16	Cement pointing to basement	Sqr.	2·76		
17	White-washing two coats	,,	31·65		
18	Burnt brick in morter coping 1½' thick over compound wall including plastering.	R.ft.	54		
19	Flooring with 1st Class Mangalore tiles on 3" concrete including cement pointing.	Sqr.	3·89		
20	Gravel flooring consolidated including lead and cowdung wash.	,,	2·50		
21	Clearing site, etc.	Lump sum			
22	Cornice 9"	R.ft	26		
23	Honne wood eave board plain including chocolate painting.	,,	101		
24	Jambs of doors and windows in burnt brick in mortar and unforeseen items.	Lump sum			
25	Water trough, complete.	Lump sum			
	Constructing three blocks of quarters at Kalasa, Mudgere Taluk.				
				Rs. a. p.	
1	Earthwork excavation for foundation and filling basement gravelly soil.	C.yd.	29		
2	Stone jelly concrete in chunam mortar ...	C.ft.	350		
3	Rough stone in mud with 3¾ mile lead for stones.	C.yd.	755		
4	Burnt brick in mud with bonds, etc., as per specification of mariots.	C.ft.	954		
5	Burnt brick in mortar	,,	267		

Serial No.	Particulars of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
6	Burnt stone slabs 4" thick roughly dressed and fixed.	S.ft.	74		
7	Honne or matti battened doors with frame hinges, bolts, etc., complete.	,,	108		
8	Honne or matti wood battened windows with frame, iron bars, hinges, screws, etc., complete.	,,	9		
9	Honnewood or matti battened ventilators with frame iron bars with swaying arrangements, cotton rope, etc., complete.	,,	13		
10	Chunam plastering two coats	Sqr.	24·00		
11	Nandi or matti wood wrought and put up including wood oiling.	C.ft.	62·82		
12	Roofing with 1st Class Mangalore tiles in teak reepers 1" x 1½".	Sqr.	11·46		
13	Mangalore ridge tiles set in mortar and cement pointed.	R.ft.	89		
14	Flooring with 1st Class Mangalore tiles on 3" concrete bed with cement pointing.	Sqr.	3·53		
15	Flouring with Cudapah slabs 1½" thick on 3" concrete bed including cement pointing.	,,	1·03		
16	Burnt stone pillars nicely dressed ...	S.ft.	32		
17	Cutting grooves in pillars	No.	4		
18	White washing two coats	Sqr.	22·69		
19	Chunam pointing	,,	1·67		
20	Providing wall shelves on pegs with jungle wood planks.	S.ft.	12		
21	Providing links	No.	1		
22	Providing mortar and pestle	,,	1		
23	Painting doors with chocolate painting two coats and wood oiling inside.	Sqr.	3·11	5·00	
24	Constructing latrine complete	L. S.			
25	Tarring to wood-work	L. S. Sqr.	5·00		
26	Clearing site and levelling ground ...	Lump sum			
27	Coping over with compound wall with plastering, complete.	R.ft.	22		
28	Honney wood eave board including chocolate painting.	,,	61		

L. A. H. WINCKLER,
Executive Engineer.

GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Abstract Notification.

Attention of the public is invited to the detailed Notification dated the 20th November 1930, calling for tenders for constructing the Staff Quarters at Mysore published in Part VI, page 1456 to 1458 of the *Mysore Gazette*, dated 4th December 1930.

The latest date for receiving tenders is 2 P.M., on 15th December 1930.

C. M. CARIAPPA,
Chief Electrical Engineer.